

NOTES

1. DO NOT SCALE.
2. ALL OPERATIVES TO HAVE ASBESTOS AWARENESS TRAINING.
3. ROUTES TO BE REVIEWED AGAINST EXISTING SERVICE DRAWINGS TO ENSURE ALL KNOWN SERVICES ARE IDENTIFIED.
4. CAT SCANS TO BE CARRIED OUT ALONG PROPOSED ROUTES PRIOR TO EXCAVATION.
5. AREAS IDENTIFIED ON SERVICE DRAWINGS AND CAT SCANS AS HAVING THE POTENTIAL OF EXISTING SERVICES TO BE HAND DUG ONLY.
6. ENSURE A BANKSMAN IS IN PLACE AT ALL TIMES WHEN EXCAVATING USING MECHANICAL DIGGERS.
7. ALL DIGGING TO BE CARRIED OUT WITH CAUTION IN REGARDS TO BROWN FIELD SITES. SHOULD A CONCERN BE RAISED DURING EXCAVATING WORKS IN REGARDS TO THE TYPE OF SOIL, CONTAMINANTS OR ADJACENTS, WORKS ARE TO BE STOPPED IMMEDIATELY AND THE AREA IS TO BE TAKEN PLACE AND A REGISTERED REPRESENTATIVE HAS CONFIRMED THE AREA IS SAFE.
8. PLEASE REFER TO DRAWING 519685-PT-01 FOR DETAILS OF THE CABLE PITS AND TRENCHES.
9. PLEASE REFER TO DRAWING 519685-INT-01 FOR DETAILS AT BUILDING ENTRY POINTS.

Blue arrow shows location of remaining civil works 3.1.2018

Rev	Description	Date	Eng
Client			



EMCOR Group (UK) plc
Premier House, Tollymore
Eastleigh, Hampshire, SO53 3YE
Tel No. 02380 641641
Fax No. 02380 641100

Project
Brunel University

Title
PHASE 2
WORK PACK 07 – Civil Works
Gaskell Building

Discipline
NETWORK SOLUTIONS

Status

PROPOSED

Drawn	SS	Checked	NC	Size	A1
Job No	519685	Scale	1:200	Date	17/07/17
Drawing No	519685-P2-WP07	Rev	A		

